

INTER-CAP LOAN

Elementary Bathrooms:

Remove existing sinks and countertops

Install new counter tops

Install new Sinks & faucets

New plumbing (drains and water supply lines)

Replace Partitions

Dispose of all waste

Middle School Cabinets:

Remove old and install new Cabinets

Dispose of old Cabinets

5 classrooms consisting of approximately 18 ft. each of lower and upper cabinets.

(Cabinets to match style and design of cabinets in rooms 246 & 250)

(Touch up painting on wall to be done in house before new cabinets are installed)

Football Bleacher:

Remove and replace all wood above main framing with weather resistant wood

New stairs (east and west ends)

New stair railing

New safety railing with safety wire around entire Bleacher seating area

Fasten all wood with Deck screws (no nails)

Dispose of old wood

Sidewalks

Remove and replace approx. 3800 sq.ft. Of Sidewalk

Dispose of old sidewalks

Side walk to be no less than 4" thick with rebar placed to code

Attach new sidewalks to existing sidewalks with rebar

Top of sidewalk to be at ground level on street side (no step) and slight slope away from buildings for water drainage

If needed Remove first section of ramp going in to the Elementary to match up with new sidewalk

