



Tony Baldwin, Ed.D., Superintendent

175 Bingham Road, Asheville, NC 28806
P 828.255.5921 F 828.255.5923
www.buncombe.k12.nc.us

ADDENDUM #1

MAY 18, 2016

TRANSMITTED VIA EMAIL: 1 page

TO: ALL PLAN HOLDERS AND POTENTIAL BIDDERS
FROM: RON VENTURELLA, PURCHASING OFFICER *RV*
SUBJECT: BLEACHER MOTORIZATION & GYM FLOOR REPLACEMENT
CANE CREEK MIDDLE SCHOOL
(RFP# 20-16)

The following changes, revisions, additions, and/or clarifications to the plans and/or specifications are hereby made a part of the original documents. **Be sure to acknowledge this addendum on the proposal sheet.**

Addendum # 1
RFP #07-16

1. Alternate (1) Painting of Gymnasium Ceiling: Ceiling color to be Flat Black Sherwin Williams "DryFall" paint.
2. Vented cove base shall stop at the closure location of the bleachers. (Wall area where bleachers physically are back to the limit). So as to allow for additional ventilation.
3. Bleacher contractor shall be required to provide motorization (either permanent or temporary) to pull the bleacher out to the middle of the floor till flooring installation is complete.
4. Bleacher pendant control shall be located on the South, exterior wall at the end of the extended bleacher bank.

END OF ADDENDUM #1
BLEACHER MOTORIZATION & GYM FLOOR REPLACEMENT
CANE CREEK MIDDLE SCHOOL (RFP# 20-16)