



ADDENDUM #3

March 16, 2016

Food Lab Renovations at North Buncombe & Clyde A. Erwin High Schools Food Lab Renovations at Enka High School Buncombe County Schools, Asheville, NC

The following changes, revisions, additions, and/or clarifications to the original plans, specifications, and/or other construction documents are hereby made a part of the original documents. Bidders shall acknowledge receipt of this addendum by notation in the space provided on the Form of Proposal.

Please staple this and all addenda inside the front cover of the project manual.

GENERAL ITEMS - APPLICABLE TO BOTH PROJECTS

Item 53 Change of Bid Date

Refer to the Project Manual, Notice to Bidders, Advertisement for Bids, Request for Proposal. Bids were not opened on March 16. The Projects have been readvertised. **Bids will be received until 2:00 PM on March 24, 2016 at the address shown in the Project Manual.**

Item 54 Controls Systems

Refer to the Drawings, North Buncombe Sheets M0.1 and M1.1, and Enka Sheets M0.1 and M1.1. The existing HVAC controls systems are to remain in place and operational. Thermostats are to be relocated where indicated on the mechanical plans. The new exhaust and makeup air systems have their own controls and do not interface with the buildings' HVAC control systems.

NORTH BUNCOMBE AND ERWIN HIGH SCHOOLS ONLY

Item 55 Downdraft Hoods

Refer to the Project Manual, Section 11 3100 Appliances. Change the basis of design model for the downdraft hood to Faber SCIR3014SS.

Item 56 Canopy Finishes

Refer to the Project Manual, Section 05 5000 Metal Fabrications, and the Drawings, Sheets NB SP1.1 and Erwin SP1.1. Provide a brushed finish for all exposed stainless steel members included in the canopy construction included in Alternate 1 North Buncombe Site Improvements (refer to Details 5 and 6/SP1.1) and in Alternate 3 Erwin High School Site Improvements (refer to Details 2 and 3/SP1.1).

End of Addendum #3