

Joiner Sheet Metal and Roofing

205 Madison St
Highland, IL 6224
5/2/2019

Office: (618) 664-9488
Fax: (618) 664-9441
Mobile : (618) 581-0121
email: sean@joinersmr.com

Roofing Material & Labor Quote:
Staunton School
Staunton, IL
ATTENTION BRIAN

***Fully adhered TPO Roof Installation: approximately 4,750 square ft.**

- Tear off all existing wall and curb flashings
- Fasten a layer of 2.5" secureshield ISO over the existing EPDM roof on area K and on area G we will overlay approximately 1,100 sq. ft. with ¼" securerock both will be mechanically fastened to the deck 1 fastener per every 2 sq. ft.
- Adhere a 060 EPDM membrane on both areas
- Installation of all new wall and curb flashings
- Install termination bar into existing gutters and into the existing masonry walls.
- Supply a 20 year 90 mph manufacturer's roof warranty on area K

Roofing Total **\$30,242.00**

Notes:

1. If bad roof deck is found it will be repaired on a time and material basis.
2. This price will be good for 60 days

Respectively Submitted: Sean Engelmann Date: 5/2/2019

Contract Acceptance: _____ Date: _____